



**Jones Gillam Renz Architects**

**Address**

730 N 9th St.  
Salina, KS 67401

1881 Main St., Suite 301  
Kansas City, MO 64108

**Contact**

jgr@jgrarchitects.com  
(785) 827-0386

**Web**

jgrarchitects.com

**NOTICE TO ALL CONTRACTORS AND SUB-CONTRACTORS**

**July 15, 2024**

**Astra Bank – Operations Building – JGR Proj #24-3424**

**Bid Date:** Friday, July 19, 2024 by 2:00 p.m.

**ADDENDUM NO. 2**

YOU ARE INSTRUCTED TO READ AND TO NOTE THE FOLLOWING DESCRIBED CHANGES, CORRECTIONS, CLARIFICATIONS, OMISSIONS, DELETIONS, ADDITIONS, APPROVALS, AND STATEMENTS PERTINENT TO THE CONTRACT AND CONSTRUCTION DOCUMENTS. THIS ADDENDUM IS A PART OF THE CONTRACT AND CONSTRUCTION DOCUMENTS AND SHALL GOVERN IN THE PERFORMANCE OF THE WORK.

**CIVIL – Specifications**

1. Clarifications:
  - A. Maximum aggregate shall comply with Table 1116-2 of the latest version of Section 1116 of the KDOT Standard Specifications.
  - B. Fine and Coarse Aggregates: ASTM C33: Refer to Section 1116 of the KDOT Standard Specifications (Table 1116-3).

**ARCHITECTURAL – Drawings**

1. Sheet A10.1, Door Schedule – Reference attached revised door schedule.

**ARCHITECTURAL – Specifications**

2. Section 06410 Custom Casework, paragraph 2.05B – Color of quartz shall be selected from full line of Category 4 at a later date.
3. Section 07620 Sheet Metal Flashing and Trim, paragraph 2.01B – Color of soffit material shall match cast stone (light color) at Main Entry soffit. Architect to select from manufacturer's full range of colors.
4. Section 07631 Gutters and Downspouts, paragraph 2.01A – Gutters and downspouts are not required to be seamless. However, they must be in 20 foot lengths minimum. Do not install seams above door or window locations.
5. Section 09688 Carpet – Glue Down
  - A. Add the following paragraph 1.07 Allowances
    - 1) Cash Allowance: This contractor shall install and furnish all carpet. This contractor shall allow the sum of \$35.00 per square yard for purchase and delivery of carpet only.
    - 2) Allowance includes the purchase and delivery of carpet only. Installation, glue and accessories are to be included in the Contractor's Bid price, **not** the allowance. Any differential in the allowance amount listed above and original invoices from the mill/manufacturer will be adjusted in the contract price.
  - B. Delete paragraph 2.01 in it's entirety. Carpet will be selected from either J&J Industries, Patcraft, Mohawk, or Shaw.

**STRUCTURAL – Drawing**

1. Sheet S0.1, General Notes, 3 Concrete, paragraph C Exterior Flatwork – Exterior flatwork shall be 4,000 psi.

Receipt of this Addendum shall be noted on the Bid Form.

END OF ADDENDUM NO. 2

Attachments  
Revised Door Schedule – 1 pg.

## DOOR SCHEDULE

MARK	DOOR						FRAME				DETAILS	REMARKS
	SIZE			MATERIAL		TYPE	MATERIAL		TYPE			
	W	H	T	ALUMINUM	S.C. WOOD	TYPE	ALUMINUM	HOLLOW METAL	TYPE			
101	3'-0"	7'-0"	1 3/4"	●		A	●		3		A-A4.2 & G,H,J,K,L,M,N,O,P-A10.1	1,3
102	3'-0"	7'-0"	1 3/4"	●		A	●		4		A-A4.2 & N,O,P,Q,R,S-A10.1	1,3
103	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
104	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
105	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
106	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
107	3'-0"	7'-0"	1 3/4"	●		B	●		1		G,H,L,T-A10.1	1,2,3
108	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
109	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
111	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
112	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
113	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
114	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
115	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
116	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
117	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
118	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	3
119	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	
121	3'-0"	7'-0"	1 3/4"	●		B	●		1		G,H,L,T-A10.1	1,2,3
122	3'-0"	7'-0"	1 3/4"		●	B		●	2		E,F-A10.1	

**NOTES:**

1. CONTRACTOR MUST INSTALL MTL. FLASHINGS & CAULK FOR A WEATHER & WATERTIGHT CONDITION ● ALL EXTERIOR DOORS & DOOR FRAMES/UNITS.
2. PROVIDE & INSTALL TWO PEEPHOLES. VERIFY HEIGHTS WITH ARCHITECT.
3. DOORS & FRAMES SHALL BE PREPARED FOR ELECTRIC STRIKE. DOOR IS ON ACCESS CONTROL SYSTEM.



730 N. Ninth St. 1881 Main Street, Suite 301  
 Salina, KS 67401 Kansas City, MO 64108  
 785.827.0386 jgr@jgarchitects.com

### ASTRA BANK - OPERATIONS BUILDING REVISED DOOR SCHEDULE HAYS, KANSAS

DATE: 7-12-2024  
 JOB #: 24-3224

# 1